



**PAMBANSANG PUNONGHIMPILAN TANOD BAYBAYIN NG PILIPINAS  
(National Headquarters Philippine Coast Guard)**

139 25<sup>th</sup> Street, Port  
Area 1018 Manila

30 September 2022

**SUPPLEMENTAL/BID BULLETIN NO. 02-2022**

This Supplemental/Bid Bulletin No. **02-2022** is issued to clarify all the prospective bidders regarding the schedule of procurement activities for the project **Renovation of HSG Office** detailed as follows:

**Section VI. Specifications**

**Scope of Works**

10. Supply of materials, tools and equipment for the new installation of roof steel framing system and Rib-Type Color Roof cover complete with all the necessary accessories and as indicated in the plan including the application of epoxy primer paints for metals, installation of Roof Thermal Insulation, 10mm thick x 1m. x 50m. and provision for a water tight installation as indicated in the plan.

**Section IX. Checklist of Technical and Financial Documents**

**I. Technical Component Envelope**

**(g)** Statement of the bidder's Single Largest Completed Contract (SLCC) similar to the contract to be bid, which must be at least equivalent to **fifty percent (50%)** of the ABC or in the amount of **Eight Hundred Seventy Thousand Five Hundred Nineteen Pesos and Sixty-Five Centavos (PhP870,519.65)**

**Annex II. Bill of Quantities**

**PROJECT TITLE : RENOVATION OF HSG OFFICE**  
**LOCATION : NHPCG 139 25TH ST. PORT AREA,**  
**MANILA, 1018**  
**OWNER : PHILIPPINE COAST GUARD**

ITEM NO	DESCRIPTION	QTY	UNIT	MATERIAL COST	AMOUNT
<b>ARCHITECTURAL WORKS</b>					

<b>I</b>	<b>MASONRY WORKS</b>				
	<b>Concreting Works</b>				
01	Ground Floor @Mess Hall (slab fill)	9.50	cum		
	<i>Sleeping area Extension @ Commander's Office</i>				
02	Ground Floor (slab fill)	2.16	cum		
	<i>1.644 meter Extension</i>				
03	Ground Floor (slab fill)	2.86	cum		
	<i>Phase 2 Extension</i>				
04	Ground Floor (slab fill)	10.77	cum		
	<b>Masonry Works</b>				
	<i>Commander's Quarter Extension</i>				
05	Demolition of Existing Wall CHB Wall	5.54	sq.m.		
06	CHB 4" Walls	23.40	sq.m.		
07	Painting	23.40	sq.m.		
	<i>Phase 2 Extension</i>				
08	Demolition of Existing Wall	17.50	sq.m.		
09	CHB 4" Walls	82.98	sq.m.		
10	Painting	82.98	sq.m.		
	<b>Wall Plastering</b>				
11	Wall Plastering	129.79	sq.m.		
	<b>Sub - Total I</b>				
<b>II</b>	<b>CEILING FINISHES</b>				
	<i>Office Area</i>				
01	Dismantling of Ceiling	109.40	sq.m		
02	12mm Gypsum Board on Metal Furring	109.40	sq.m		
03	Painting	109.40	sq.m		
	<b>Commander's Office-Sleeping Area</b>				
04	Dismantling of Ceiling at CO and Deputy	24.57	sq.m		
05	12mm Gypsum Board on Metal Furring;	24.57	sq.m		
06	Painting	24.57	sq.m		
	<b>Commander's Office-Toilet and Bath</b>				
07	Dismantling of Ceiling	2.12	sq.m		
08	12mm Moisture Resistance Gypsum Board on Metal Furring	2.12	sq.m		
09	Painting	2.12	sq.m		
	<b>RECSTA's Office-Toilet and Bath</b>				

10	Dismantling of Ceiling	2.12	sq.m		
11	12mm Moisture Resistance Gypsum Board on Metal Furring	2.12	sq.m		
12	Painting	2.12	sq.m		
	<b>Office Extension</b>				
13	Dismantling of Ceiling	36.23	sq.m		
14	12mm Moisture Resistance Gypsum Board on Metal Furring	36.23	sq.m		
15	Painting	36.23	sq.m		
	<b>Deputy Commander's Office-Toilet and Bath</b>				
16	Dismantling of Ceiling	1.80	sq.m		
17	12mm Moisture Resistance Gypsum Board on Metal Furring	1.80	sq.m		
18	Painting	1.80	sq.m		
	<b>PEU Office-Toilet and Bath</b>				
16	Dismantling of Ceiling	2.10	sq.m		
17	12mm Moisture Resistance Gypsum Board on Metal Furring	2.10	sq.m		
18	Painting	2.10	sq.m		
	<b>Sub - Total II</b>				
<b>III</b>	<b>WALL FINISHES</b>				
	<i>Dry Wall @ Commander's Office</i>				
01	12mm Gypsum Board on Metal Studs	42.11	sq.m		
02	Painting	42.11	sq.m		
	<i>Drywall @ Office Extension</i>				
03	12mm Gypsum Board on Metal Studs	108.67	sq.m		
04	Painting	108.67	sq.m		
	<i>Wall Tiles @ Commander's toilet and bath</i>				
05	300mmx300mm Homogenous Tiles	12.57	sq.m		
	<i>Wall Tiles @ PEU toilet and bath</i>				
06	300mmx300mm Homogenous Tiles	15.12	sq.m		
	<i>Wall Tiles @ Deputy Commander's toilet and bath</i>				
07	300mmx300mm Homogenous Tiles	13.92	sq.m		
	<b>Sub - Total III</b>				
<b>IV</b>	<b>FLOOR FINISHES</b>				
	<b>Office</b>				
01	Dismantling of 30x30 tiles	75.90	sq.m		

02	Finish:FF 01-600mmx600mm Glazed Tiles	109.40	sq.m		
	<b>Commander's Office</b>				
03	Dismantling of 30x30 tiles at CO and Deputy	22.80	sq.m		
04	Finish:FF 01-600mmx600mm Glazed Tiles	24.57	sq.m		
	<b>Commander's Quarter</b>				
05	Dismantling of 30x30 tiles	5.70	sq.m		
06	Finish:FF 01-600mmx600mm Glazed Tiles	5.70	sq.m		
	<b>Commander's Office-Toilet and Bath</b>				
07	Dismantling of Tiles	2.12	sq.m		
08	FF 02-300mmx300mm Unglazed Tiles non-skid	2.12	sq.m		
09	Lavatory, water closet and shower set	1.00	lot		
	<b>Office Extension</b>				
10	Dismantling of Tiles	36.23	sq.m		
11	FF 02-300mmx300mm Unglazed Tiles non-skid	36.23	sq.m		
	<b>Deputy Commander's Office-Toilet and Bath</b>				
12	Dismantling of Tiles	1.80	sq.m		
13	FF 02-300mmx300mm Unglazed Tiles non-skid	1.80	sq.m		
14	Lavatory, water closet and shower set	1.00	lot		
	<b>PEU Office-Toilet and Bath</b>				
15	Dismantling of Tiles	2.10	sq.m		
16	FF 02-300mmx300mm Unglazed Tiles non-skid	2.10	sq.m		
17	Lavatory, water closet and shower set	1.00	lot		
	<b>Sub - Total IV</b>				
<b>V</b>	<b>WATER PROOFING WORKS</b>				
	<b>Commander's Office-Toilet and Bath</b>				
01	All Toilets	6.02	sq.m.		
	Others to complete works (List below)				
	<b>Sub - Total V</b>				
<b>VI</b>	<b>DOORS</b>				
01	WD1- 0.70X2.10 Hollow Core Door, both sides Marine Plywood	7.00	sets		

02	WD2- 0.60X2.10 Hollow Core Door, 1 side Marine Plywood; with louvers	4.00	sets		
	<b>Sub - Total VI</b>				
<b>VII</b>	<b>ROOFING</b>				
01	Rib-Type Color Roof	28.00	sq.m		
02	Trusses	28.00	sq.m		
03	Pre-Painter Gutter, GA 24 (0.701 MM) x 2.44m	9.00	ln.m		
04	Roof Thermal Insulation, 10mm THK x 1m x 50m	1.00	rolls		
	<b>Sub - Total VII</b>				
<b>VIII</b>	<b>ELECTRICAL WORKS</b>				
	<b>THHN (Branch Circuits)</b>				
	<b>WIRES AND CABLES</b>				
01	3.5 mm <sup>2</sup> Cu Cond Strnd	4.00	rolls		
02	5.5 mm <sup>2</sup> Cu Cond Strnd	1.00	rolls		
	<b>TW (Grounding)</b>				
03	3.5 mm <sup>2</sup> Cu Cond Strnd	2.00	rolls		
04	5.5 mm <sup>2</sup> Cu Cond Strnd	1.00	rolls		
	<b>PIPES AND FITTINGS</b>				
05	20 mm Ø x 3m	65.00	lgths		
06	25 mm Ø x 3m	35.00	lgths		
	<b>WIRING DEVICES</b>				
07	One-Way, One-Gang Switch	12.00	sets		
08	One-Way, Two-Gang Switch	1.00	sets		
09	One-Way, Three-Gang Switch	2.00	sets		
10	Duplex Conv Outlet w/ ground	31.00	sets		
11	ACU Convenience Outlet	4.00	sets		
	<b>LIGHTING FIXTURES</b>				
12	2 x 18W LED FF	17.00	units		
13	1 x15W LED Downlight	12.00	units		
	<b>BOXES AND CONDULETS</b>				
14	Junction box 4x4 w/ Cover	80.00	pcs		
15	Utility box 2x4	50.00	pcs		

<b>MISCELLANEOUS AND HARDWARES</b>					
16	Electrical Tape	2.00	bndls		
17	Rubber Tape	3.00	rolls		
18	Hacksaw Blade	3.00	pcs		
19	Ga #14 GI Pull Wire	3.00	kgs		
20	PVC Cement, 120cc	4.00	cans		
21	5mm x 300mm Cable Ties	1.00	pcks		
22	Exhaust Fan Ceiling Mounted	4.00	units		
	<b>Sub - Total VIII</b>				
	<b>GRAND TOTAL</b>				

**AMOUNT IN WORDS:**

---

Name and Signature of Bidder's Representative:

---

Date:

---

Position:

---

Name of Company

---

For guidance and information of all concerned.



**CG LTJG ZAIRA MARGARETTE R DE CHAVEZ**  
Chairman, HSG Bids and Awards Committee

Received by the Bidder:

---

Date: